

# West Square Parking Lot Pavement Replacement Addendum

## Reference section from RFP

2.1 Base aggregate dense - 3/4" - Furnish and place material following Section 305 of Wisconsin DOT Standard Specifications. Payment will be by the Ton placed.

2.3 **Section B** (closest to the building) will need to be completed first.

2.4 Old pavement may be removed with a backhoe or milled down to the subgrade

2.9 The entire lot will be re-striped. 23 stalls will be numbered for county vehicles. There will be 6 handicap stalls to be painted per ADA compliance, curbs are to be re-painted blue. (see diagram A below)

The contractor shall replace the five (5) plastic parking curbs in the handicap stalls closest to the building with rubber parking curbs.

All concrete curbs are to remain in place.

The alley is not included in the scope of the project.

## Diagram A:

