

West Square/LEC Caulking Project Addendum

All doors and door frames need to have existing caulk removed and replaced with new caulk

All windows will need to have glazing removed and replaced with new glazing.

Horizontal caulk joints at ground level do not need to be removed and replaced.

The wall by loading dock westside of the West Square building will need to be crack filled and new overlay coating put on.

Law Enforcement Center original caulk was Tremco 511 2 part mix for all horizontal and vertical precast panels and door frames - Amarillo White.

West Square's original caulk was Tremco Dymeric Polyurethane Terpolymer Sealant. No color on file. Please find the best matching color.

See attached documents for elevations.